


SWMU 19 AND 20 GEOPHYSICAL REPORT



EARTH RESOURCES TECHNOLOGY, INC.

March 1, 2002

Amanda DeSantis
Montgomery Watson Harza, Inc.
335 Phoenixville Pike
Malvern, PA 19355

Re: Results of Geophysical Surveys
Honeywell International Facility
Claymont, DE

Dear Amanda:

Earth Resources Technology, Inc. (ERT) performed electromagnetic (EM) and GPR surveys at the above referenced site on Wednesday, February 27, 2002. These surveys were conducted at two separate sites to determine the locations of specific features and targets. EM surveys were conducted at Solid Waste Management Units (SWMUs) 19 and 20. The EM surveys were conducted to determine the location of buried metallic objects such as gas cylinders and under ground storage tanks (USTs). The GPR surveys were conducted at SWMUs 19 and 20 to better define any anomalies that were located during the EM survey. The goal of the GPR survey was to better define the location and depths of the buried objects.

1.0 Principle And Instrumentation

The Geonics EM31 was used for the electromagnetic survey. The EM31 measures the changes in the ground conductivity using a patented electromagnetic inductive technique that makes the measurements without electrodes or ground contact. The unit of conductivity used is millisiemens per meter (mS/m). Conductivity changes are used to infer the geological variations, or groundwater contamination. The EM31 has two analog meters, which display the quadrature-phase (conductivity) and inphase components, respectively. Inphase measurements are the ratio of the induced secondary magnetic field to the primary magnetic field in parts per thousand (ppt). The inphase component is especially useful for searching for buried metal drums, pipes, and other ferrous and non-ferrous metallic debris. The effective depth of exploration of the equipment is about twenty (20) ft.

The pulseEKKO 1000 radar from Sensors & Software, Inc. was used to conduct the GPR survey. During the survey, the device radiates a 450 MHz electromagnetic wave from a transmitter antenna into the earth and receives at a receiving antenna the reflection of the wave from subsurface interfaces at which changes in the electrical properties (dielectric permittivity and electrical conductivity) of the subsurface materials occur. Dielectric permittivity controls wave speed; and conductivity determines the signal attenuation. Radar reflections occur when the radio waves encounter a change in the velocity or attenuation. The bigger the change in properties the more signal reflected. These properties are sometimes controlled by water in the material, hence by the porosity and quantity of dissolved solids in the water. Metallic objects usually exhibit strong subsurface reflection character due to their high electrical impedance, or contrast, versus surrounding soil or fill. Depth of penetration of the radar signal is inversely proportional to the

conductivity of the soil. As a result, electrically resistive earth materials such as coarse-grained, unsaturated sediments allow a deeper radar penetration than the conductive finer-grained soils such as clay and silt. Similarly, reinforced concrete and shallow groundwater are conductive and thus attenuate the radar signals.

2.0 SHMU 19

2.1 Field Design and Operation

The goal of the survey was to locate areas within a pre-determined site that may contain buried metallic objects such as gas cylinders and USTs. The suspect grid for SHMU 19 is located near the BF3 plant area. The area was for the most part was paved asphalt and flat with minor immovable obstructions. As shown in Figure 1, the survey was conducted along a grid that was based on a Cartesian coordinate system with fiducial marks every 5 ft. The grid was 45 ft by 325 ft. For example, the origin of the coordinate system on the grid is located adjacent to the railroad tracks in the northwest corner of the designated site and has the coordinates {100, 100}. During the data collection, the EM31 was set in a manual mode with readings collected at 5-ft centers along each survey line in both quadrature-phase and inphase.

Figure 2 shows the location of the GPR survey lines. The inphase contour map (discussed at Section 2.2) is shown here as background. The collection of the GPR data was performed by pulling the antenna along each grid line while the positions of each radar reading were recorded with an odometer attached to a survey wheel. The odometer was set up such that one radar reading would be acquired every 0.05 m (0.164 ft). Because the subject property is underlain by the artificial fill or clay/silt/sand, the average velocity of the radar is estimated around 0.1 m (0.328 ft) per nanosecond (ns). The time range was thus selected as 70 ns and would allow a penetration depth of about 10 ft. The GPR data were recorded digitally in a portable computer for instant display and subsequent processing.

2.2 Results and Interpretations

In Figure 3, the EM anomalies are shown with the highest readings in orange and the lowest readings in blue. Background readings fall between the orange and blue colors. Note that the low or high conductivity/inphase values are not absolute, but relative, reflecting a deviation from the background values. The positive or negative values reflect the change of the dipole orientation of the local electromagnetic field. Both the high and low deviations are used to locate buried materials. There are several large anomalies in the grid area that is associated with known surface features. Anomaly E along the north edge of Figure 3 is associated with the railroad tracks on the property. Anomaly F of Figure 3 is associated with a large tank on the ground surface. Anomaly G of Figure 3 is associated with large trucks on the property. There are several anomalous readings that show up on Figure 3 that cannot be accounted for by surface features and therefore are areas of concern for buried metallic objects. Anomaly A of Figure 3 is in the area of concern for a suspected UST. Anomalies B and C are linear anomalies and may represent possible underground pipelines. Anomaly B may correspond to one utility but C to two utility lines. Anomaly D may be another area of concern for buried metallic objects.

Figures 4 through 7 present several selected GPR profiles that were acquired during the geophysical survey (see Figure 2 for their locations). Along these GPR profiles, the horizontal axis represents the horizontal distance in ft; while the left vertical axis represents the two-way travel time in ns and the right vertical axis the depth in ft (converted using the assumed velocity of 0.328 ft/ns). A GPR profile is made of individual traces that have peaks and valleys. The peaks of radar signals represent different interfaces

in the subsurface encountered by the penetrating signals. Connecting and coloring the peaks and valleys of successive traces creates a GPR profile. As shown in the profiles, the red reflections represent the peaks of individual traces with the highest amplitudes; while the blue reflections are the valleys of individual traces with the lowest amplitudes. The red color is replaced by dark gray of varying degrees for the lower peak amplitudes; and the blue by white for varying degrees of higher valley amplitudes. The red and blue reflections, as discussed in Section 1.0, are created by interfaces with higher dielectric contrasts.

Figure 4 shows GPR profile A-A' that was acquired across EM anomaly A and B. Corresponding to Anomaly A, strong, "ringing" but flat reflections occur at the distances between 18 ft and 28 ft at the depth of 2 ft. On top of the "ringing" reflections is a reflector typical of a reinforced concrete slab. Corresponding to Anomaly B is a hyperbolic reflector typical of a pipe at the distance of 39 ft at the depth of 2 ft. In addition, strong but somewhat chaotic reflections occur at the depths less than 2 ft at the distances between 3 ft and 15 ft, between 28.5 ft and 35 ft, and between 49 ft and 56 ft, respectively. These reflections are typical of buried debris or foundations.

Profile B-B' crossed EM anomaly A in the direction perpendicular to A-A' (Figure 5). Beneath a reinforced concrete slab, ringing but flat reflections occur between 18 ft and 27 ft at the depth of 2 ft. The reflections correspond in location to Anomaly A and the ringing reflections on A-A'. The ringing reflections may represent the suspected UST. However, the flat characteristics of the reflections suggest that they may represent a foundation structure unless the UST has a flat top surface. A weak hyperbolic reflector is also identified on B-B' at the distance of 3 ft at the depth of 1 ft.

Figure 6 presents two GPR profiles, C-C' and D-D' acquired across EM anomaly D. Strong, ringing and flat reflections occur on both profiles with concrete slabs on the top. These reflections are similar to the ringing reflections on A-A' and B-B'. They may represent a possible flattop UST or foundation structure. Profile E-E' ran across linear EM anomaly C (Figure 7). Two pipe-like reflectors are identified at the locations corresponding to Anomaly C. Ringing reflectors are also identified near the end of E-E' and may represent foundations.

In order to interpret the 2-dimensional, vertical GPR profile data in a 3-dimensional perspective, EKKO Mapper Software, developed by Sensors and Software was used. Using this software, GPR profiles are gridded and the data gaps between grid lines are extrapolated. A 3-D block is created from this data. The 3-D block can be viewed and displayed as time or depth slices. Each slice takes the form of a contour map of reflection amplitudes. Figure 8 shows two timeslices of the data set. The colors on the maps show averaged, enveloped amplitudes of radar reflections over an interval of two-way travel time (in nanoseconds, or ns) of the radar signal. Migration, noise filtering, and background subtraction were also applied to the data sets. Many timeslices (1 to 2 ns, 2 to 3 ns, ..., 14 to 15 ns) were created and analyzed by ERT, but only two are shown in this report (others did not show anything significantly different from these two). Site features and the grid are also shown.

Figure 8 shows five areas of concern labeled GA, GB, GC, GD, and GE. Anomaly GA represents the strong but chaotic reflections at the distances between 3 ft and 15 ft. Based on the fact that the areas of strong amplitude (white) constitute a narrow strip enclosing a square, the anomaly may represent foundation walls. Anomaly GB corresponds to the ringing reflections identified on A-A' (Figure 4) and B-B' (Figure 5). Because it is located in the area of concern of a possible UST and there is a corresponding EM anomaly (A), the anomaly may represent a UST that has a flat top surface. Anomaly GC is a linear anomaly and corresponds to the pipe reflector identified on A-A'. Its location matches that of EM anomaly B. The anomaly most likely represents a utility line. Anomaly GD corresponds to the strong but chaotic reflections at the distances between 49 and 56 ft on A-A' (Figure 4). It may represent buried debris or abandoned foundation. Anomaly GE does not have any corresponding GPR profile on

display. However, the review of the GPR profiles in this area reveals strong but chaotic reflections. Therefore, the anomaly may represent an area with abandoned foundation or buried debris.

3.0 SHMU 20

3.1 Field Design and Operation

The goal of the survey was to locate areas within a pre-determined site that may contain buried metallic objects such as gas cylinders and USTs. The suspect area for SHMU 20 is located near the BF3 plant area. The area was for the most part was paved asphalt and flat with minor immovable obstructions. As shown in Figure 9, the survey was conducted along a grid that was based on a Cartesian coordinate system with fiducial marks every 5 ft. The grid for the EM survey was 80 ft by 60 ft. During the data collection, the EM31 was set in a manual mode with readings collected at 5-ft centers along each survey line in both quadrature-phase and inphase.

The GPR grid extended another 15 ft to the east of the EM grid (Figure 10). This was done to cover an anomaly identified with the GPR on the eastern edge of the original EM grid. The inphase contour map was also shown on the map as background. The collection of the GPR data was performed by pulling the antenna along each grid line while the positions of each radar reading were recorded with an odometer attached to a survey wheel. The odometer was set up such that one radar reading would be acquired every 0.05 m (0.164 ft). Because the subject property is underlain by the artificial fill or clay/silt/sand, the average velocity of the radar is estimated around 0.1 m (0.328 ft) per nanosecond (ns). The time range was thus selected as 70 ns and would allow a penetration depth of about 10 ft. The GPR data were recorded digitally in a portable computer for instant display and subsequent processing.

3.2 Results and Interpretations

In Figure 11, the EM anomalies are shown with the highest readings in orange and the lowest readings in blue. There are several large anomalies in the grid area that is associated with known surface features. Anomaly C along the north edge of Figure 11 is associated with trucks on the property. Anomaly B of Figure 11 is associated with a concrete pad on the ground surface. Anomaly A shows up as anomalous readings on both the quadrature and in-phase maps and can not be explained by any surface features.

Figures 12 and 13 present GPR profiles that were acquired during the geophysical survey. The location of the GPR profiles are shown in Figure 10 and labeled as A-A' and B-B'. Both profiles crossed EM anomaly A. On profile A-A' (Figure 12) there are strong reflections from 0 ft to 26 ft representing disturbed areas at a depth of 2 ft to 3 ft. The concrete pad at the end of A-A' also creates strong reflections. On profile B-B' (Figure 13), the strong reflections from 0 ft to 32 ft correspond to the strong reflections representing disturbed areas as identified on A-A'. The reflections occur at the depth from 1 to 3 ft. These strong reflections on both A-A' and B-B' appear to be continuous and therefore may not represent isolated objects. They may be buried material laid out as layers. A pipe-like reflector is also identified on B-B' at a distance of 85 ft and a depth of 2 ft. In addition, Figure 13 shows that there is a relatively undisturbed area from 33 ft to 78 ft where no material is buried. Strong reflections occur less than 2 ft in depth at the end of B-B'.

Figure 14 presents four GPR time slice maps (0-5, 5-10, 10-15, and 15-20ns) of the area of concern for SWMU 20. This figure is used to show how the average amplitude changes with depth. These figures show four areas of concern labeled GF, GG, GH, and GI. Anomaly GF encompasses the bottom third of all the maps and shows the highest amplitude reflections of the surveyed area. The anomaly corresponds to the areas labeled as "Disturbed Area?" on Figure 12 and Figure 13. This feature shows up best on


maps B and C and represents an area of concern for buried material. Because this area corresponds to EM anomaly A, it may represent a landfill material.

Anomaly GG is associated with the known concrete pad (Figure 14). Anomaly GH refers to the two linear features that cross the surveyed area and are linked to two metal grates. This anomaly most likely represents buried pipes. Anomaly GI that shows up best on Map B corresponds to the strong reflections observed at the end of B-B' and may be an area of concern for buried objects.


4.0 CLOSING

The field procedures and interpretative methodologies used in this project are consistent with standard, recognized practices in similar geophysical investigations. The correlation of geophysical responses with probable subsurface features is based on the past results of similar surveys although it is possible that some variation could exist at this site. This warranty is in lieu of all other warranties either implied or expressed. **ERT** assumes no responsibility for interpretations made by others based on work performed by, or recommendations made by, **ERT**.

Sincerely,
Earth Resources Technology, Inc.

A handwritten signature in black ink, appearing to read 'Peter H. Li', is written over the printed name.

Peter H. Li, Ph.D., P.G.
Principal Geophysicist



SWMU 19 SITE MAP
HONEYWELL INTERNATIONAL
CLAYMONT, DE PLANT


EARTH RESOURCES TECHNOLOGY



FIGURE 1

SCALE: 1" = 50'

MARCH 1, 2002



SWMU 19 GPR LINES
HONEYWELL INTERNATIONAL
CLAYMONT, DE PLANT



EARTH RESOURCES TECHNOLOGY





FIGURE 2

SCALE 1" = 50"

MARCH 1, 2002



A: Quadrature
(Conductivity)



B: In-phase

ELECTROMAGNETIC CONTOUR MAPS
SWMU #19
HONEYWELL INTERNATIONAL
CLAYMONT, DE PLANT


EARTH RESOURCES TECHNOLOGY



FIGURE 3

SCALE: 1" = 40'

MARCH 1, 2002




EARTH RESOURCES TECHNOLOGY

SCALE AS SHOWN

GPR PROFILE A-A'
SWMU 19 GPR SURVEY
HONEYWELL INTERNATIONAL PLANT
CLAYMONT, DE

FIGURE 4

MARCH 1, 2002





EARTH RESOURCES TECHNOLOGY

SCALE AS SHOWN

GPR PROFILE B-B'
SWMU 19 GPR SURVEY
HONEYWELL INTERNATIONAL PLANT
CLAYMONT, DE

FIGURE 5

MARCH 1, 2002




EARTH RESOURCES TECHNOLOGY

SCALE AS SHOWN

GPR PROFILES C-C' AND D-D'
SWMU 19 GPR SURVEY
HONEYWELL INTERNATIONAL PLANT
CLAYMONT, DE

FIGURE 6

MARCH 1, 2002




EARTH RESOURCES TECHNOLOGY

SCALE AS SHOWN

GPR PROFILE E-E'
SWMU 19 GPR SURVEY
HONEYWELL INTERNATIONAL PLANT
CLAYMONT, DE

FIGURE 7


MARCH 1, 2002



A. AVERAGE AMPLITUDE 0-10ns



B. AVERAGE AMPLITUDE 10-20ns



0 250(500(75010001250150017500

AVERAGE AMPLITUDE (mV)

GPR TIME SLICE MAP 10-20 ns
SWMU 19
HONEYWELL INTERNATIONAL
CLAYMONT, DE PLANT


EARTH RESOURCES TECHNOLOGY



FIGURE 8

SCALE 1" = 20'

MARCH 1, 2002



SWMU 20 SITE MAP
HONEYWELL INTERNATIONAL
CLAYMONT, DE PLANT


EARTH RESOURCES TECHNOLOGY



FIGURE 9

SCALE: 1" = 20'

MARCH 1, 2002



SWMU 20 GPR LINE BASE MAP
HONEYWELL INTERNATIONAL
CLAYMONT, DE PLANT


EARTH RESOURCES TECHNOLOGY




FIGURE 10

SCALE 1" = 20'

MARCH 1, 2002



A: Quadrature (Conductivity)



B: In-phase




EARTH RESOURCES TECHNOLOGY

SWMU 20
ELECTROMAGNETIC MAPS
HONEYWELL INTERNATIONAL
CLAYMONT, DE PLANT

FIGURE 11

SCALE: 1" = 20'

MARCH 1, 2002




EARTH RESOURCES TECHNOLOGY

SCALE AS SHOWN

GPR PROFILE A-A'
SWMU 20 GPR SURVEY
HONEYWELL INTERNATIONAL PLANT
CLAYMONT, DE

FIGURE 12

MARCH 1, 2002








EARTH RESOURCES TECHNOLOGY

SCALE AS SHOWN

GPR PROFILE B-B'
SWMU 20 GPR SURVEY
HONEYWELL INTERNATIONAL PLANT
CLAYMONT, DE

FIGURE 13

MARCH 1, 2002



GPR TIME SLICE MAPS
SWMU 20
HONEYWELL INTERNATIONAL
CLAYMONT, DE PLANT

EARTH RESOURCES TECHNOLOGY



FIGURE 14

SCALE 1" = 30'

MARCH 1, 2002

APPENDIX C
TEST PIT LITHOLOGIC LOGS



MWH
MONTGOMERY WATSON HARZA


MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM13-TP01

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/15/03
Date Finished: 4/15/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Southern perimeter of SWMU 13
Total Depth (ft): 4.3'
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Clear, 70's
Logged By: S. Bouclier, Geologist





MWH
MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM13-TP02

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Across Geophysics Boundary
Project Number:	2110876	Total Depth (ft):	3.0'
Date Started:	4/15/03	Water Level During Drilling (ft/bgs):	NA
Date Finished:	4/15/03	Weather Conditions:	Clear, 70's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
0.0		SAND AND GRAVEL: 0.0-0.75' Dark brown, medium to coarse-grained SAND and subangular GRAVEL, dry.	
0.0			
0.1			
0.0	SILT AND SAND: 0.75-2.0' Light gray, SILT and fine-grained SAND, dry to damp, moderately firm. In center of trench trace to little brick, plastic and coarse-grained gravel.		
0.0			
1.0			
0.2			
0.1			
3.4			
0.5	SILT: 2.0-3.0' Tan to mauve with light gray to white mottles, SILT, some oxidation, little clay, moist, firm.		
0.0			
0.0			
0.3			
0.0			
-1			
-2			
-3			

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM13-TP03**

Page 1 of 1

Project Name: Honeywell-Claymont**Location:** Claymont, DE**Project Number:** 2110876**Date Started:** 4/15/03**Date Finished:** 4/15/03**Drilling Company:** Lewis Environmental**Drilling Method:** Backhoe**Sampling Method:** Backhoe Bucket**Test Pit Location:** Across Geophysics Boundary**Total Depth (ft):** 1.5'**Water Level During Drilling (ft/bgs):** NA**Weather Conditions:** Clear, 80's**Logged By:** S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0			
0.1		SAND AND GRAVEL: 0.0-1.0' Dark brown, medium to coarse-grained SAND and subangular GRAVEL, dry.	
0.0			
0.4			
3.1			
5.0			
0.8			
53.2		SAND AND GRAVEL: 1.0-1.5' Dark brown, medium to coarse-grained SAND and fine to medium-grained subangular GRAVEL, dry.	
41.7			
11.2			
-1			Refusal at 1.5', thick concrete slab that extends entire length of trench.

**MWH**


MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM13-TP04**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/15/03
Date Finished: 4/15/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Across Geophysics Boundary
Total Depth (ft): 7.5'
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Clear, 70's
Logged By: S. Bouclier, Geologist



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM13-TP05**

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Estimated Location of Buried Drums
Project Number:	2110876	Total Depth (ft):	5.0'
Date Started:	4/29/03	Water Level During Drilling (ft/bgs):	NA
Date Finished:	4/29/03	Weather Conditions:	Clear, 70's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
39.7			
29.2			
11.4		SAND AND GRAVEL: 0.0-1.0' Dark brown, medium to coarse-grained SAND and subangular GRAVEL, some brick and concrete, dry, loose.	
-1			
8.6		SAND AND SLAG: 1.0-4.0' Dark brown to black with some white, medium to coarse-grained SAND and SLAG, some brick, saturated at 3.0'.	At 1' bgs, large reinforced concrete slab approximately 30' long beginning 9' from western end of trench.
9.2			
-2			
151			
55.5			
78.2			
-3			
98.9			
76.7			
55.2			
-4			
0.7		SILT: 4.0-5.0' Beige with orange mottles, SILT, trace to little clay, dry to damp, firm.	
1.8			
0.0			
-5			



MWH
MONTGOMERY WATSON HARZA


MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM13-TP06

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/29/03
Date Finished: 4/29/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Northern Perimeter of SWMU
Total Depth (ft): 5.0'
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Clear, 70's
Logged By: S. Bouclier, Geologist



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM13-TP07**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/16/03
Date Finished: 4/16/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Across Geophysics Boundary
Total Depth (ft): 11.0'
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Clear, 70's
Logged By: S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0			
961		SAND AND GRAVEL: 0.0-2.0' Dark brown, medium to coarse-grained SAND and subangular GRAVEL, dry, loose.	
-1			
322			
1067			
-2			
915		SILT: 2.0-10.0' Tan with reddish mottles, SILT, little clay, dry, firm, some black staining. At 7.0', lense of gray fine to medium-grained sand.	
564			
-3			
742			
1008			
-4			
879			
1258			
-5			
654			
954			
-6			
1389			
2879			
-7			
3269			
7660			
-8			
5213			
3441			
-9			
1115			
1067			
-10			
365		SILT: 10.0-11.0' Pink with trace tan mottles, SILT, little clay, dry, firm.	
20.8			
40.3			
-11			




MWH
MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM14-TP01

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Western perimeter, into truck parking lot
Project Number:	2110876	Total Depth (ft):	3.0'
Date Started:	4/14/03	Water Level During Drilling (ft/bgs):	2.6'
Date Finished:	4/14/03	Weather Conditions:	Overcast, 40's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM14-TP02**

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Southern perimeter, west of chiller
Project Number:	2110876	Total Depth (ft):	2.6'
Date Started:	4/14/03	Water Level During Drilling (ft/bgs):	NA
Date Finished:	4/14/03	Weather Conditions:	Overcast, 40's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0	0.0	SAND: 0.0-1.25' Brown, coarse-grained SAND, some brick and construction debris, trace to little silt, dry.	At 1.5' concrete slab present.
-1	0.0	SAND AND BRICK: 1.25-1.75' Brown, coarse-grained SAND and BRICK, concrete slab, dry.	
-2	0.0	SILT: 1.75-2.3' Tan with beige to orangish mottles, SILT, trace clay, dry, firm.	

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM14-TP03**

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Southeast of AST
Project Number:	2110876	Total Depth (ft):	3.2'
Date Started:	4/14/03	Water Level During Drilling (ft/bgs):	
Date Finished:	4/14/03	Weather Conditions:	Overcast, 40's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
0.0		SAND: 0.0-0.5' Brown, fine to medium-grained SAND, little silt, dry, trace rootlets.	
0.0			
0.0		BRICK: 0.5-2.5' BRICK, some slag, little to some blue-green medium to coarse-grained sand (copper waste), trace medium to coarse-grained sand, moist to wet. Saturated at 2.2'.	
0.0			
-1			
0.0			
0.0			
0.0			
0.0			
-2			
0.0			
0.0			
0.0		SILT: 2.5-3.2' Tan with beige to orangish mottles, SILT, trace clay, damp, firm.	
0.0			
-3			

**MWH**

MONTGOMERY WATSON HARZA


MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM14-TP04**


Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/14/03
Date Finished: 4/14/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Eastern Perimeter along fence
Total Depth (ft): 4.0'
Water Level During Drilling (ft/bgs):
Weather Conditions: Overcast, 40's
Logged By: S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0			
0.0		SAND AND GRAVEL: 0.0-1.0' Brown, medium to coarse-grained SAND and GRAVEL, dry, abundant rootlets.	
0.0			
0.0			
0.0			
-1		SAND AND GRAVEL: 1.0-3.0' Gray brown, medium to coarse-grained SAND and GRAVEL, some asphalt, trace to little bricks, damp.	
0.0			
0.0			
0.0			
0.0			
-2			
0.0			
0.0			
0.0			
0.0			
-3		SILT: 3.0-4.0' Tan with beige and orange mottles, SILT, little clay, damp, firm.	
0.0			
0.0			
0.0			
0.0			
-4			

 MWH MONTGOMERY WATSON HARZA		MWH Americas, Inc. 335 Phoenixville Pike Malvern, Pennsylvania 19355	Test Pit ID: SM14-TP05 Page 1 of 1
Project Name: Honeywell-Claymont Location: Claymont, DE Project Number: 2110876 Date Started: 4/14/03 Date Finished: 4/14/03 Drilling Company: Lewis Environmental Drilling Method: Backhoe	Sampling Method: Backhoe Bucket Test Pit Location: Northeast from AST on diagonal Total Depth (ft): 3.8' Water Level During Drilling (ft/bgs): 2.6' Weather Conditions: Overcast, 40's Logged By: S. Bouclier, Geologist		



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM14-TP06**

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Northern perimeter
Project Number:	2110876	Total Depth (ft):	3.8'
Date Started:	4/14/03	Water Level During Drilling (ft/bgs):	
Date Finished:	4/14/03	Weather Conditions:	Overcast, 40's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0	0.0	SAND: 0.0-0.5' Brown, medium to coarse-grained SAND, some medium to coarse-grained gravel, little silt, trace bricks and blue-green medium to coarse-grained sand (copper waste), moist.	At 1.0' bgs, concrete slab running across trench.
0.0	0.0	BRICK: 0.5-1.5' BRICK and degraded brick, little to some blue-green medium to coarse-grained sand and gravel (copper waste), damp to wet. Saturated at 1.25'.	
-1	0.0	SILT: 1.5-2.0' Tan with beige to orange mottles, SILT, trace clay, damp, firm.	
-2	0.0		

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM15-TP01**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/8/03
Date Finished: 4/8/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: North of Former Storage Area
Total Depth (ft): 3.5'
Water Level During Drilling (ft/bgs): 3.5'
Weather Conditions: Overcast, 50's
Logged By: S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0			
0.7		SILT AND SAND: 0.0-2.0' Dark brown SILT and fine-grained SAND, moist, moderately firm.	
0.0			
0.0			
0.0			
-1			
11.8		SILT: 2.0-2.5' Black with trace oxidation, SILT, damp, moderately firm. At ~2.25' color changes to olive to dark brown with lenses of black and oxidation.	
5.7			
0.0			
0.0			
-2			
58.2		DEBRIS: 2.5-3.0' CONSTRUCTION DEBRIS (bricks, wood, glass), little silt, moist.	
47.3			
65.1			
2.3			
-3			
5.7		SILT: 3.0-3.5' Greenish gray and brown with some oxidation, SILT, little clay, trace to little fine-grained sand, trace lenses of black silt, wet. At 3.5' saturated.	
8.7			
3.9			
2.4			

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM15-TP02**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/8/03
Date Finished: 4/8/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: East of Former Storage Area
Total Depth (ft): 5.0'
Water Level During Drilling (ft/bgs): 2.0'
Weather Conditions: Overcast, 50's
Logged By: S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0		SAND: 0.0-0.5' Dark brown, medium-grained SAND, some silt, moist, abundant rootlets.	
0.0			
0.0			
-1		SAND: 0.5-1.0' Dark brown, medium-grained SAND, layers of oxidation, moist.	
0.0			
0.0			
-1		SAND: 1.0-1.5' Dark brown, medium-grained SAND, some black silt and little clay, moist.	
0.0			
0.0			
-2		SILT: 1.5-2.0' Black, SILT, some oxidized medium-grained sand, little clay, moist, moderately firm.	
0.0			
0.0			
-2		SILT: 2.0-3.0' Black, SILT and CONSTRUCTION DEBRIS (bricks, coarse-grained subangular gravel, wood, trace glass), some oxidized medium-grained sand, little clay, saturated.	
0.0			
0.0			
-3		SILT: 3.0-5.0' Tan with red to bluish gray mottles, SILT, trace to little clay, damp, firm.	
0.0			
0.0			
-4			
0.0			
0.0			
-5			
			At approximately 3.0', there is a large concrete slab extending 10' from the western edge of the trench to the eastern end of the trench, ~30'.

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM15-TP03**

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Southern side of SWMU, along gravel road
Project Number:	2110876	Total Depth (ft):	2.5'
Date Started:	4/8/03	Water Level During Drilling (ft/bgs):	2.5'
Date Finished:	4/8/03	Weather Conditions:	Overcast, 50's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
0.0		DEBRIS: 0.0-2.5' CONSTRUCTION DEBRIS (asphalt, concrete, bricks, coarse-grained subangular gravel, wood, glass), some dark brown silt and fine to medium-grained sand, moist to wet.	
0.0			
0.0			
0.0			
-1			
0.0			
0.0			
0.0			
0.0			
0.0			
0.0			
0.0			
-2			
0.0			
0.0			
			Refusal at 2.5', large concrete slab extending entire length of trench. Possibly the same slab seen at SM15-TP02

**MWH**


MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM15-TP04**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/9/03
Date Finished: 4/9/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Eastern Side, along gravel road
Total Depth (ft): 5.0'
Water Level During Drilling (ft/bgs):
Weather Conditions: Overcast, 50's
Logged By: S. Bouclier, Geologist



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM15-TP05**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/9/03
Date Finished: 4/9/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Eastern Side, along gravel road
Total Depth (ft): 3.0'
Water Level During Drilling (ft/bgs):
Weather Conditions: Rain, 50's
Logged By: S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0			
0.0		SILT AND SAND: 0.0-1.6' Dark brown, SILT and fine to medium-grained SAND, some construction debris (brick, concrete, coarse-grained subangular gravel) abundant rootlets, moist.	
0.0			
0.0			
-1			
0.0			
0.0			
0.0			
0.0		DEBRIS: 1.6-2.5' CONSTRUCTION DEBRIS (abundant brick, coarse-grained subangular gravel, wood, trace glass), some grayish tan silt and medium-grained sand, moist to wet. Construction debris not as abundant towards eastern side of test pit.	At depth 1.6' concrete slab present. Possibly the same concrete slab seen at SM15-TP02 and SM15-TP03.
-2			
0.0			
0.0			
0.0		SILT: 2.5-3.0' Grayish tan with greenish gray mottles, SILT, little clay, damp, firm.	
-3			

**MWH**


MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM15-TP06**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/9/03
Date Finished: 4/9/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Northeast Corner
Total Depth (ft): 3.5'
Water Level During Drilling (ft/bgs):
Weather Conditions: Rain, 40's
Logged By: S. Bouclier, Geologist

PID Reading		Lithology	Geologic Description	Remarks
0	0.0		SILT: 0.0-0.5' Orangish tan with gray mottles, SILT, little clay, trace fine-grained sand, moist, moderately firm, abundant rootlets.	
	0.0			
	0.0		DEBRIS: 0.5-3.0' CONSTRUCTION DEBRIS (brick, coarse-grained gravel, glass), some brown, silt and medium-grained sand, moist.	
-1	0.0			
	0.0			
	0.0			
	0.0			
-2	0.0			
	0.0			
	0.0			
	0.0			
-3	0.0		SILT: 3.0-3.5' Grayish tan, mottled, SILT, little clay, damp, firm.	
	0.0			

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM15-TP07**

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	North Side, near utility poles
Project Number:	2110876	Total Depth (ft):	5.0'
Date Started:	4/10/03	Water Level During Drilling (ft/bgs):	4.0'
Date Finished:	4/10/03	Weather Conditions:	Overcast, 40's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
0.0		SILT: 0.0-0.5' Orangish tan, SILT, little coarse-grained subangular gravel, trace fine-grained sand, moist, moderately firm, abundant rootlets.	
0.0			
0.0		DEBRIS: 0.5-4.0' CONSTRUCTION DEBRIS (abundant asphalt, concrete, coarse-grained subangular gravel, brick, trace glass), some silt, trace to little fine-grained sand, moist to wet.	Construction debris present entire length of trench but not as abundant towards north end of test pit.
0.0			
-1			
0.0			
0.0			
0.0			
0.0			
-2			
0.0			
0.0			
0.0			
0.0			
-3			
0.0			
0.0			
0.0			
0.0			
-4		SILT: 4.0-5.0' Grayish tan, SILT, trace to little clay, damp, firm.	
0.0			
0.0			
0.0			
0.0			
-5			

**MWH**


MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM15-TP08**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/10/03
Date Finished: 4/10/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: West side near large debris piles
Total Depth (ft): 5.0'
Water Level During Drilling (ft/bgs):
Weather Conditions: Overcast, 40's
Logged By: S. Bouclier, Geologist



**MWH**


MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP01**

Page 1 of 1

Project Name: Honeywell-Claymont SWMU 17
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/30/03
Date Finished: 4/30/03
Drilling Company: TerraProbe
Drilling Method: Geoprobe

Sampling Method: Geoprobe Macrocore
Boring Location: In Front of Tank Entrance
Total Depth (ft): 7.0'
Boring Diameter (in): 2"
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Clear, 70's
Logged By: S. Bouclier, Geologist



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP02**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	17' North of Tank
Project Number:	2110876	Total Depth (ft):	4.0'
Date Started:	4/30/03	Boring Diameter (in):	2"
Date Finished:	4/30/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist

Blow Counts	Recovery (inches)	PID Reading	Lithology	Geologic Description	Remarks
0				ASPHALT: 0.0-0.5' Asphalt, some medium to coarse-grained gravel, dry.	
		0.0		SAND AND GRAVEL: 0.5-1.0' Grayish brown, medium to coarse-grained SAND and GRAVEL, dry.	
-1				SILT: 1.0-1.7' Tan with brown and black mottles, SILT with some gravel, damp, moderately firm.	
		0.0		SAND AND GRAVEL: 1.7-2.0' Black, coarse-grained SAND and GRAVEL, wet.	
-2	36"			SILT: 2.0-2.3' Greenish gray with gray mottles, SILT, damp, moderately firm.	
		0.0		SILT: 2.3-4.0' Dark gray, SILT, little clay, dry, moderately firm, little organics.	
-3					
-4		0.0			

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP03**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	12' North of Tank
Project Number:	2110876	Total Depth (ft):	4.0'
Date Started:	4/30/03	Boring Diameter (in):	2"
Date Finished:	4/30/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist

Blow Counts	Recovery (inches)	PID Reading	Lithology	Geologic Description	Remarks
				ASPHALT: 0.0-0.7' Asphalt, some medium to coarse-grained gravel, dry.	
		57.4			
				SAND AND GRAVEL: 0.7-1.4' Brown, medium to coarse-grained SAND and GRAVEL, dry.	
		135			
				SILT: 1.4-2.0' Grayish brown with brown and black mottles, SILT, dry, moderately firm.	
	42"	35.4		SILT: 2.0-4.0' Greenish gray with black mottles, SILT, little clay, dry, moderately firm.	
		0.0			
		0.0			


**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP04**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	15' North of Tank
Project Number:	2110876	Total Depth (ft):	4.0'
Date Started:	4/30/03	Boring Diameter (in):	2"
Date Finished:	4/30/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP05**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	Northeast side of Tank
Project Number:	2110876	Total Depth (ft):	4.0'
Date Started:	4/30/03	Boring Diameter (in):	2"
Date Finished:	4/30/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist

Blow Counts	Recovery (inches)	PID Reading	Lithology	Geologic Description	Remarks
0				ASPHALT: 0.0-0.6' Asphalt and coarse-grained gravel, dry.	
-1		6.2		SILT: 0.6-2.5' Greenish gray with gray mottles, SILT, dry. Alternating lenses of black, medium-grained gravel and slag.	
-2	48"	56.2			
		26.3		SILT: 2.5-3.2' Black, SILT, lenses of brick, dry, moderately firm. At 3.2', some organics.	
-3				SILT: 3.2-4.0' Gray, SILT, some clay, dry, some organics, moderately firm.	
-4		16.8			


**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP06**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	Northeast side of Tank
Project Number:	2110876	Total Depth (ft):	4.0'
Date Started:	4/30/03	Boring Diameter (in):	2"
Date Finished:	4/30/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist





MWH
MONTGOMERY WATSON HARZA


MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Boring ID: SM17-GP07

Page 1 of 1

Project Name: Honeywell-Claymont SWMU 17
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/30/03
Date Finished: 4/30/03
Drilling Company: TerraProbe
Drilling Method: Geoprobe


Sampling Method: Geoprobe Macrocore
Boring Location: Northwest side of Tank
Total Depth (ft): 12'
Boring Diameter (in): 2"
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Clear, 70's
Logged By: S. Bouclier, Geologist






Page 1 of 1

Sampling Method:	Geoprobe Macrocore
Boring Location:	Northwest side of Tank
Total Depth (ft):	8.0'
Boring Diameter (in):	2"
Water Level During Drilling (ft/bgs):	NA
Weather Conditions:	Clear, 70's
Logged By:	S. Bouclier, Geologist






Page 1 of 1

Logged By: S. Bouclier, Geologist

Remarks



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP10**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	2' South of Tank
Project Number:	2110876	Total Depth (ft):	12.0'
Date Started:	5/1/03	Boring Diameter (in):	2"
Date Finished:	5/1/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist

Blow Counts	Recovery (inches)	PID Reading	Lithology	Geologic Description	Remarks
0				ASPHALT AND GRAVEL: 0.0-1.0' ASPHALT and coarse-grained GRAVEL, dry.	
-1		498			
-2	48	159		SAND AND GRAVEL: 1.0-2.0' Medium brown, medium to coarse-grained SAND and GRAVEL, damp.	
-3		130		SILT: 2.0-2.5' Tan with gray to black mottles, SILT, trace clay, dry.	
-4		484		SILT: 2.5-3.7' Greenish gray, SILT, trace to little clay, dry, little organics. Interbedded layers of black silt with little to some clay.	
-5		36.2		CLAY: 3.7-8.0' Gray with tan and dark gray mottles, CLAY, some silt, dry, soft.	
-6	48	56.5			
-7		155			
-8		48.2			
-9		132		SILT: 8.0-11.0' Light gray with dark gray mottles, SILT, little clay, dry, firm.	
-10	48	92.6			
-11		311			
-12		0.0		SAND: 11.0-12.0' Dark gray to black, fine to medium-grained SAND, moist.	



MWH
MONTGOMERY WATSON HARZA


MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Boring ID: SM17-GP11

Page 1 of 1

Project Name: Honeywell-Claymont SWMU 17
Location: Claymont, DE
Project Number: 2110876
Date Started: 5/1/03
Date Finished: 5/1/03
Drilling Company: TerraProbe
Drilling Method: Geoprobe

Sampling Method: Geoprobe Macrocore
Boring Location: 8' South of Tank
Total Depth (ft): 12.0'
Boring Diameter (in): 2"
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Clear, 70's
Logged By: S. Bouclier, Geologist



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP12**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	13' South of Tank
Project Number:	2110876	Total Depth (ft):	8.0'
Date Started:	5/1/03	Boring Diameter (in):	2"
Date Finished:	5/1/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist

Blow Counts	Recovery (inches)	PID Reading	Lithology	Geologic Description	Remarks
				ASPHALT: 0.0-1.0' ASPHALT, some gravel, dry.	
		690			
				SAND AND GRAVEL: 1.0-2.0' Medium brown, medium to coarse-grained SAND and GRAVEL, dry.	
		742			
	36			SILT: 2.0-3.5' Tan with brown, black and olive mottles, SILT, little to some clay, dry, moderately firm.	
		1290			
				SILT: 3.5-8.0' Greenish gray with tan mottles, SILT, little to some clay, dry.	
		137.4			
		180			
	45				
		50.8			
		479			
		11.0			


**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP13**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	18' South of Tank
Project Number:	2110876	Total Depth (ft):	12'
Date Started:	5/1/03	Boring Diameter (in):	2"
Date Finished:	5/1/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP14**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	23' South of Tank
Project Number:	2110876	Total Depth (ft):	4.0'
Date Started:	5/1/03	Boring Diameter (in):	2"
Date Finished:	5/1/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist

Blow Counts	Recovery (inches)	PID Reading	Lithology	Geologic Description	Remarks
				TOPSOIL: 0.0-0.4' Dark brown, TOPSOIL, moist, abundant rootlets.	
		0.0		SLAG: 0.4-1.0' Dark brown to black, SLAG, trace coarse-grained sand and gravel, dry.	
				SILT: 1.0-3.0' Tan with gray to black mottles, SILT, dry, firm.	
	40	0.0			
		0.0			
				SLAG: 3.0-3.5' Blue gray to red, SLAG, dry, wood fragments.	
		0.0		CLAY: 3.5-4.0' Gray with trace red mottles, CLAY, some silt, dry, trace organics, moderately firm.	

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP15**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	Southeast side of Tank
Project Number:	2110876	Total Depth (ft):	4.0'
Date Started:	5/1/03	Boring Diameter (in):	2"
Date Finished:	5/1/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist

Blow Counts	Recovery (inches)	PID Reading	Lithology	Geologic Description	Remarks
				ASPHALT: 0.0-0.6' ASPHALT and coarse-grained GRAVEL, dry.	
		0.0		SILT: 0.6-2.0' Dark tan with red to orange to black mottles, SILT, dry, firm. Black slag at 1.8'.	
		0.0			
	42			SILT: 2.0-3.2' Greenish gray with gray to black mottles, SILT, little clay, dry, firm.	
		12.8			
				SLAG AND GRAVEL: 3.2-3.5' Black SLAG and medium-grained GRAVEL, dry.	
		0.0		SILT: 3.5-4.0' Dark gray to black, SILT, little clay, dry, firm.	


**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP16**

Page 1 of 1

Project Name:	Honeywell-Claymont SWMU 17	Sampling Method:	Geoprobe Macrocore
Location:	Claymont, DE	Boring Location:	Southwest side of Tank
Project Number:	2110876	Total Depth (ft):	12'
Date Started:	5/1/03	Boring Diameter (in):	2"
Date Finished:	5/1/03	Water Level During Drilling (ft/bgs):	NA
Drilling Company:	TerraProbe	Weather Conditions:	Clear, 70's
Drilling Method:	Geoprobe	Logged By:	S. Bouclier, Geologist



**MWH**


MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Boring ID: SM17-GP17**

Page 1 of 1

Project Name: Honeywell-Claymont SWMU 17
Location: Claymont, DE
Project Number: 2110876
Date Started: 5/1/03
Date Finished: 5/1/03
Drilling Company: TerraProbe
Drilling Method: Geoprobe

Sampling Method: Geoprobe Macrocore
Boring Location: Southwest of Tank
Total Depth (ft): 4.0'
Boring Diameter (in): 2"
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Overcast, 70's
Logged By: S. Bouclier, Geologist



**MWH**


MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM18-TP01**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/22/03
Date Finished: 4/22/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Northern perimeter of geophysics boundary
Total Depth (ft): 5.0'
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Overcast, 50's
Logged By: S. Bouclier, Geologist



**MWH**


MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM18-TP02**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/22/03
Date Finished: 4/22/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Western Perimeter towards boneyard
Total Depth (ft): 3.0'
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Overcast, 50's
Logged By: S. Bouclier, Geologist




**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM18-TP03**

Page 1 of 1

Project Name: Honeywell-Claymont**Location:** Claymont, DE**Project Number:** 2110876**Date Started:** 4/22/03**Date Finished:** 4/22/03**Drilling Company:** Lewis Environmental**Drilling Method:** Backhoe**Sampling Method:** Backhoe Bucket**Test Pit Location:** Western Perimeter towards boneyard**Total Depth (ft):** 6.0'**Water Level During Drilling (ft/bgs):** NA**Weather Conditions:** Rain, 50's**Logged By:** S. Bouclier, Geologist



MWH
MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM18-TP04

Page 1 of 1

Project Name: Honeywell-Claymont

Location: Claymont, DE

Project Number: 2110876

Date Started: 4/23/03

Date Finished: 4/23/03

Drilling Company: Lewis Environmental

Drilling Method: Backhoe

Sampling Method: Backhoe Bucket


Test Pit Location: Continuation of TP-02

Total Depth (ft): 4.5'

Water Level During Drilling (ft/bgs): NA

Weather Conditions: Overcast, 50's

Logged By: S. Bouclier, Geologist



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM19-TP01**

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Next to utility poles
Project Number:	2110876	Total Depth (ft):	3.2'
Date Started:	4/16/03	Water Level During Drilling (ft/bgs):	NA
Date Finished:	4/16/03	Weather Conditions:	Clear, 80's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
45.7		SAND AND GRAVEL: 0.0-0.5' Dark brown, medium to coarse-grained SAND and subangular GRAVEL, little oxidation, lenses of clayey silt and trace bricks, dry.	
63.3			
5.4			
44.4			
180		SILT: 0.5-1.0' Grayish brown, SILT, little clay and brick, dry, firm.	
45.4			
63.8			
168			
-1			
42.7		SAND: 1.0-2.75' Black to dark brown, medium to coarse-grained SAND, some grayish brown silt and brick, little clay, trace to little slag, glass and wood, moist to saturated at 2.5'.	
35.3			
5.7			
14.9			
188			
205			
595			
642			
-2			
94.7			
132			
54.6			
38.3			
334			
134			
95.2		SILT: 2.75-3.2' Light gray to dark gray with white and brown mottles, SILT, little clay, dry.	
165			
-3			
22.7			



MWH
MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM19-TP02

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/16/03
Date Finished: 4/16/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Next to Railroad tracks
Total Depth (ft): 2.5'
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Clear, 80's
Logged By: S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0			
11.0		SAND AND GRAVEL: 0.0-1.0' Dark brown, medium to coarse-grained SAND and subangular GRAVEL, little to some gray silt with orange mottles, dry.	
6.5			
3.4			
0.0			
19.2			
5.4			
1.0			
1.0			
-1			
156		SILT AND SAND: 1.0-2.0 Black, SILT and tan, medium to coarse-grained SAND, trace clay, moist to wet.	
3.4			
0.1			
19.2			
1569			
167			
18.8			
13.3			
-2			
313		SILT: 2.0-2.5' Light gray to dark gray with white and brown mottles, SILT, little clay, dry.	
212			
13.2			
8.7			



MWH
MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM19-TP03

Page 1 of 1

Project Name: Honeywell-Claymont

Location: Claymont, DE

Project Number: 2110876

Date Started: 4/16/03

Date Finished: 4/16/03

Drilling Company: Lewis Environmental

Drilling Method: Backhoe

Sampling Method: Backhoe Bucket

Test Pit Location: Northern Perimeter of SWMU 19

Total Depth (ft): 2.3'

Water Level During Drilling (ft/bgs): NA

Weather Conditions: Clear, 80's

Logged By: S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0			
908		SAND AND GRAVEL: 0.0-1.0' Dark brown, medium to coarse-grained SAND and subangular GRAVEL, trace pink to white silt, dry.	
130			
180			
107			
213			
160			
180			
330			
-1			
1892		SILT: 1.0-2.3' Light gray with white mottling, SILT, trace clay, dry, moderately firm.	
790			
164			
397			
3342			
1092			
1082			
790			
-2			
556			
487			



MWH
MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM19-TP04

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Center of SWMU 19
Project Number:	2110876	Total Depth (ft):	2.2'
Date Started:	4/16/03	Water Level During Drilling (ft/bgs):	NA
Date Finished:	4/16/03	Weather Conditions:	Clear, 80's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
760		SAND AND GRAVEL: 0.0-0.5' Dark brown, medium to coarse-grained SAND and subangular GRAVEL, dry.	
804			
668			
109			
515		SAND AND GRAVEL: 0.5-2.0' Dark brown, medium to coarse-grained SAND and GRAVEL, trace grayish green silt and orange medium to coarse-grained sand, wet at 1.0'.	
518			
601			
510			
-1			
420			
314			
107			
634			
634			
2300			
1192			
878			
-2			
1209		SILT: 2.0-2.3' Gray, SILT, little clay, dry, firm.	At 1.5' concrete in northeastern corner of test pit.

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM19-TP05**

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/16/03
Date Finished: 4/16/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Western Perimeter
Total Depth (ft): 2.7'
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Clear, 80's
Logged By: S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0			
4.7		SAND AND GRAVEL: 0.0-1.0' Dark brown, medium to coarse-grained SAND and subangular GRAVEL, dry.	At 0.5' reinforced concrete on the western side of the testpit.
3.2			
0.0			
0.1			
116			
334			
14.2			
8.9			
-1			
13.7		SILT: 1.0-2.0' Greenish, yellowish gray with black and white mottles, SILT, trace clay, wet.	
4.8			
10.2			
4.6			
114			
234			
1.7			
0.8			
-2			
7.0		SILT: 2.0-2.7' Light gray with little black and white mottles, SILT, trace clay, dry.	
1.0			
4.7			
0.3			
0.1			



MWH
MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM20-TP01

Page 1 of 1

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 4/17/03
Date Finished: 4/17/03
Drilling Company: Lewis Environmental
Drilling Method: Backhoe

Sampling Method: Backhoe Bucket
Test Pit Location: Western Perimeter
Total Depth (ft): 1.5'
Water Level During Drilling (ft/bgs): NA
Weather Conditions: Overcast, 40's
Logged By: S. Bouclier, Geologist

PID Reading	Lithology	Geologic Description	Remarks
0			
1.0		SAND AND GRAVEL: 0.0-1.0' Medium brown, medium to coarse-grained SAND and subangular GRAVEL, dry.	
0.8			
0.3			
0.7			
0.0			
0.3			
0.3			
0.0			
-1			
0.0			
0.5			
0.3			
0.0			
			Refusal at 1.5'. Concrete slab extending length of test pit.



MWH
MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM20-TP02

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Between railroad tracks and concrete
Project Number:	2110876	Total Depth (ft):	5.8'
Date Started:	4/17/03	Water Level During Drilling (ft/bgs):	NA
Date Finished:	4/17/03	Weather Conditions:	Overcast, 40's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
3.4		SAND AND GRAVEL: 0.0-1.0' Medium brown, medium to coarse-grained SAND and subangular GRAVEL, trace brick from 0.5' to 1.0', dry, loose.	
0.0			
3.9			
0.0			
-1		SILTY SAND: 1.0-2.0' Olive brown, fine to medium-grained SAND, some silt and fine to medium-grained gravel, dry.	
1.4			
1.3			
1.9			
0.5			
1.9			
0.5			
1.8			
3.5			
-2		SILT: 2.0-5.0' Olive brown, SILT, little clay and debris (slag, wood, brick, metal plates) trace fine-grained sand, dry, trace organic material.	
1.3			
0.6			
1.0			
1.2			
0.6			
0.8			
2.4			
-3			
5.4			
3.2			
0.0			
0.0			
0.0			
0.0			
0.0			
-4			
0.2			
0.0			
0.0			
0.0			
0.0			
0.0			
0.0			
-5		SILT: 5.0-5.8' Grayish tan, SILT, little clay, dry, firm.	
0.0			
0.0			
0.0			
0.0			
0.0			
0.0			
0.0			

At 1.5' deep, on the southern edge of test pit is the same concrete pad seen at SM20-TP01.

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM20-TP03**

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Northeast corner of SWMU
Project Number:	2110876	Total Depth (ft):	6.0'
Date Started:	4/17/03	Water Level During Drilling (ft/bgs):	NA
Date Finished:	4/17/03	Weather Conditions:	Overcast, 40's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
0.0		SAND AND GRAVEL: 0.0-1.0' Medium brown, medium to coarse-grained SAND and subangular GRAVEL, trace brick from 0.5' to 1.0', dry, loose.	
0.0			
0.0		SILT: 1.0-2.0' Greenish gray, SILT, little to some clay, little fine to coarse-grained sand, abundant debris (slag, wood, coarse-grained subangular gravel, brick, pipe, railroad ties, ash and cinder), dry, moderately firm.	
0.0			
-1			
1.1			
0.0			
0.0			
-2			
0.0			
0.0			
0.0			
0.0			
0.0			
-3			
0.0			
0.0			
0.0			
3.8			
0.0			
-4			
1.5			
1.8			
1.5			
0.8			
1.7			
1.3			
-5			
0.0			
0.0			
0.0			
0.0			
0.0		SILT: 5.0-5.8' Grayish tan, SILT, little clay, dry, firm.	
0.0			
0.0			
-6			

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Test Pit ID: SM20-TP04**

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Next to railroad tracks
Project Number:	2110876	Total Depth (ft):	4.0'
Date Started:	4/21/03	Water Level During Drilling (ft/bgs):	NA
Date Finished:	4/21/03	Weather Conditions:	Overcast, 50's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
0.0		SAND AND GRAVEL: 0.0-1.0' Medium brown, medium to coarse-grained SAND and subangular GRAVEL, trace brick from 0.5' to 1.0', dry, loose.	
0.0			
0.0			
0.0			
-1			
2.7		SILT: 1.0-2.0' Greenish gray, SILT, little to some clay, little fine to coarse-grained sand, abundant debris (slag, wood, coarse-grained subangular gravel, brick, pipe, railroad ties, ash and cinder), dry, moderately firm.	
1.8			
0.2			
25.5		SILT: 5.0-5.8' Grayish tan, SILT, little clay, dry, firm.	
3.4			
0.7			
-2			
3.4			
2.7			
2.1			
46.8			
12.2			
8.9			
3.4			
-3			
11.7			
8.2			
3.1			
0.2			
-4			



MWH
MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Test Pit ID: SM20-TP05

Page 1 of 1

Project Name:	Honeywell-Claymont	Sampling Method:	Backhoe Bucket
Location:	Claymont, DE	Test Pit Location:	Next to Railroad tracks
Project Number:	2110876	Total Depth (ft):	4.0'
Date Started:	4/21/03	Water Level During Drilling (ft/bgs):	NA
Date Finished:	4/21/03	Weather Conditions:	Overcast, 50's
Drilling Company:	Lewis Environmental	Logged By:	S. Bouclier, Geologist
Drilling Method:	Backhoe		

PID Reading	Lithology	Geologic Description	Remarks
0			
0.0		SAND AND GRAVEL: 0.0-1.0' Medium brown, medium to coarse-grained SAND and subangular GRAVEL, dry to moist.	
0.0			
0.0			
0.0			
-1		SAND AND GRAVEL: 1.0-1.5' Gray, medium to coarse-grained SAND and black coarse-grained, subangular GRAVEL, some slag and wood, saturated at 1.5'.	
2.7			
1.8			
0.2			
25.5		SILT: 1.5-4.0' Grayish tan, SILT, little clay, dry, firm.	
3.4			
0.7			
-2			
3.4			
2.7			
2.1			
46.8			
12.2			
8.9			
3.4			
-3			
11.7			
8.2			
3.1			
0.2			
-4			

APPENDIX D

MONITORING WELL LITHOLOGIC AND CONSTRUCTION LOGS

**MWH**


MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Well ID: MW-1**

Page 1 of 2

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 5/13/03
Date Finished: 5/13/03
Drilling Company: Talon Drilling
Drilling Method: HSA
Sampling Method: Split Spoon

Boring Location: Corner of SWMU 13 Parking Lot
Ground Elevation (ft/msl): 30.36'
Total Depth (ft): 20'
Boring Diameter (in): 4"
Water Level During Drilling (ft/bgs): 12'
Weather Conditions: Rain, 60's
Logged By: S. Bouclier, Geologist



**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Well ID: MW-1**

Page 2 of 2

Blow Counts	Recovery (inches)	PID Reading	Sample Interval	Sample Interval	USCS Symbol	Lithology	Geologic Description	Well Diagram	Remarks
12							SILT AND SAND: 12.0-12.5' Grayish tan, SILT and fine-grained SAND, trace to little medium-grained gravel, trace clay, saturated, soft, trace mica.		
12							SILT AND SAND: 12.5-15.5' Grayish tan with dark gray striations, SILT and fine-grained SAND, moist, firm, trace mica flakes.		
-13	23	24							
	23								
-14									
	27								
-15		6					SILT: 15.5-16.0' Olive green, SILT, some medium-grained gravel, dry.		
	50/5"						SAPROLITE: 16.0-20.0' White, dark gray and black, SAPROLITE, abundant mica, dry.		
-16	8								
	6								
-17	6	15							
	10								
-18	7								
	8								
-19	12	15							
	10								
-20									

2-inch
0.010 slot
PVC screen
from 9.0'
to 19.0'
bgs.Total depth
of borehole
20' bgs.

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Well ID: MW-2**

Page 1 of 2

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 5/12/03
Date Finished: 5/12/03
Drilling Company: Talon Drilling
Drilling Method: HSA
Sampling Method: Split Spoon

Boring Location: NE Corner of SWMU 15, near utility poles
Ground Elevation (ft/msl): 34.11'
Total Depth (ft): 16'
Boring Diameter (in): 4"
Water Level During Drilling (ft/bgs): 7'
Weather Conditions: Showers, 60's
Logged By: S. Bouclier, Geologist

Blow Counts	Recovery (inches)	PID Reading	Lithology	Geologic Description	Well Diagram	Remarks
0						
5		0.0		SILT AND SAND: 0.0-0.6' Dark brown, SILT and medium-grained SAND, abundant organics, damp.		Concrete pad to 0.5' bgs.
-1	13	0.0		SILT: 0.6-8.0' Light brown to beige with black to beige mottles, SILT, trace brick, dry, firm. At 6.0' color change to beige with orange to deep red mottles. At 6.5' color change to grayish beige. At 7.0' saturated. At 7.2' color change to pink with beige to orangish red colored mottles.		6-inch steel casing to 1.0' bgs.
		0.0				Grout to 2.0' bgs.
-2		0.0				Bentonite chips from 2.0' to 3.5' bgs.
	NR	NR				2-inch PVC riser from 0.0 to 4.5' bgs.
-3						
	NR	NR				
-4						
		0.0				
-5	8	0.0				#1 Sandpack from 3.5' to 16.0' bgs.
		0.0				
-6		0.0		SILT: 8.0-13.0' Pink with beige to rusty colored mottles, SILT, little clay, damp, firm.		
	18	0.0				2-inch 0.010 slot PVC screen from 4.5' to 14.5' bgs.
-8		0.0				
	14	0.0				
-9		0.0				
		0.0				
-10		0.0				
		0.0				
-11		0.0				
		0.0				
-12		0.0				
		0.0				

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Well ID: MW-2**

Page 2 of 2

Blow Counts	Recovery (inches)	PID Reading	Sample Interval	Sample Interval	USCS Symbol	Lithology	Geologic Description	Well Diagram	Remarks
-13 20 23 -14 15 18 -15 18 20 -16	18	0.0					SILT: 13.0-13.5' Pinkish beige with orange to beige mottles, SILT, little fine to medium-grained sand, trace clay, damp, firm.		
		0.0					SAND: 13.5-15.0' Pinkish beige with orange to beige mottles, fine to medium-grained SAND, trace silt and mica, damp.		
	14	0.0					SAND: 15.0-16.0' Tan with rusty colored lenses, fine to medium-grained SAND, little to some fine to medium-grained gravel, little silt, trace mica, wet.		Total depth of borehole 16' bgs.



MWH
MONTGOMERY WATSON HARZA


MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355

Well ID: MW-3

Page 1 of 2

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 5/12/03
Date Finished: 5/12/03
Drilling Company: Talon Drilling
Drilling Method: HSA
Sampling Method: Split Spoon

Boring Location: West of SWMU 18 in Boneyard
Ground Elevation (ft/msl): 30.97'
Total Depth (ft): 16'
Boring Diameter (in): 4"
Water Level During Drilling (ft/bgs): 10'
Weather Conditions: Overcast, 70's
Logged By: S. Bouclier, Geologist





Page 2 of 2

	Blow Counts	Recovery (inches)	PID Reading	Sample Interval	Sample Interval	USCS Symbol	Lithology	Geologic Description	Well Diagram	Remarks
-11	4 8 8 8	12					SAND: 10.0-13.0' Rusty brown with deep gray mottles, fine-grained SAND, trace silt and mica, saturated. At 11.8' lense of silt.			
-12	3 4									
-13	5 7	12					SAND: 13.0-13.5' Gray, fine to medium-grained SAND, trace mica flakes, saturated.			
-14	12						SAND: 13.5-14.5' Gray, fine-grained SAND, trace medium-grained sand, trace mica flakes, saturated.			
-15	14 15	14					SAND: 14.5-15.0' Medium gray, medium-grained SAND and GRAVEL, saturated, lenses of red medium-grained sand.			
-16	18						SAPROLITE: 15.0-16.0' White, dark gray, greenish beige, SAPROLITE, moist.			Total depth of borehole 16' bgs.

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
335 Phoenixville Pike
Malvern, Pennsylvania 19355**Well ID: MW-4**

Page 1 of 2

Project Name: Honeywell-Claymont
Location: Claymont, DE
Project Number: 2110876
Date Started: 5/13/03
Date Finished: 5/13/03
Drilling Company: Talon Drilling
Drilling Method: HSA
Sampling Method: Split Spoon

Boring Location: Behind Administrative Building
State Permit Number: 193565W
Ground Elevation (ft/msl): 30.5'
Total Depth (ft): 20.0'
Boring Diameter (in): 4"
Water Level During Drilling (ft/bgs): 12.5'
Weather Conditions: Overcast, 70's
Logged By: S. Bouclier, Geologist

Blow Counts	Recovery (inches)	PID Reading	Lithology	Geologic Description	Well Diagram	Remarks
0						
4		0.0		SILT AND SAND: 0.0-2.0' Medium brown, SILT and fine-grained SAND, trace mica, abundant rootlets, dry.		Concrete pad to 1.0' bgs.
8		0.0				
12	13	0.0				6-inch steel casing to 1.0' bgs.
9		0.0				
12		0.0		SILT: 2.0-7.0' Grayish tan with light gray to reddish orange mottles, SILT, trace clay and mica flakes, firm, dry. Moist from 4.0' to 4.5', dry at 4.5'.		Grout to 5.5' bgs.
15		0.0				
15	13	0.0				2-inch PVC riser from 0.0 to 9.5' bgs.
10		0.0				
8		0.0				
4		0.0				
8	12	0.0				Bentonite chips from 5.5' to 7.7' bgs.
12		0.0				
12		0.0				
12		0.0				
12	16	0.0		SILT: 7.0-8.5' Tan with light gray to reddish orange mottles, SILT, trace mica, dry, firm. Striations of reddish orange colored silt.		
15		0.0				
6		0.0				
10		0.0		SILT: 8.5-9.0' Rose to tan with mottles, SILT, dry, firm.		
10	17	0.0		SILT: 9.0-9.5' Tan with light gray to reddish orange mottles, SILT, trace mica, dry, firm.		
10		0.0				
6		0.0		SILT: 9.5-10.0' Tan with light gray to reddish orange mottles, SILT, trace clay and mica, damp.		2-inch 0.010 slot PVC screen from 9.5' to 19.5' bgs.
7		0.0				
7	8	0.0		SILT: 10.0-12.5' Tan with light gray to reddish orange mottles, SILT, little clay, trace mica, moist, soft.		
8		0.0				
8		0.0				

**MWH**

MONTGOMERY WATSON HARZA

MWH Americas, Inc.
 335 Phoenixville Pike
 Malvern, Pennsylvania 19355

Well ID: MW-4

Page 2 of 2

Blow Counts	Recovery (inches)	PID Reading	Sample Interval	Sample Interval	USCS Symbol	Lithology	Geologic Description	Well Diagram	Remarks
-13	8						SILT: 12.5-13.7' Tan with light gray to reddish orange mottles, SILT, little fine-grained sand, trace clay and mica flakes, wet at 12.5', soft.		
	10	24							
	10								
-14	2						SILT AND SAND: 13.7-14.5' Medium brown to tan, fine-grained SILT and SAND, little mica, dry, firm.		
	4								
-15	10	16					SILT AND SAND: 14.5-15.2' Medium gray, fine-grained SILT and SAND, little mica, trace clay, lenses of fine-grained sand and silt at 15.0', moist.		
	18								
-16	15						SILT AND SAND: 15.2-15.5' Orangish tan, fine-grained SILT and SAND, little mica, moist.		
	22								
-17	25	20					SAND: 15.5-16.0' Orangish tan, fine to medium-grained SAND, little silt and fine-grained gravel, moist, poorly sorted.		
	30								
-18	5						SAND: 16.0-17.2' Orangish tan, fine to medium-grained SAND, little mica, trace fine-grained gravel, moist, poorly sorted.		
	5								
-19	5	24					SAND: 17.2-18.2' Orangish tan, fine to medium-grained SAND, some medium to coarse-grained gravel, moist. Color change at 17.5' to dark grayish blue.		
	5								
-20	7						SILT: 18.2-20.0' Dark brown, SILT, little clay and mica, trace fine-grained sand, moist, soft.		

#1
 Sandpack
 from 7.7'
 to 19.5'
 bgs.

Total depth
 of borehole
 19.5' bgs.